

Addendum #2

2017-007 Landfill & Transfer Station Fencing

(1)

Reference:

V. DETAILED SPECIFICATIONS

Clarification concerning chain link size:

- **Mesh to be 9 gauge wire**

(2)

Reference:

V. DETAILED SPECIFICATIONS

Clarification concerning chain link size:

- **Mesh to have 2” opening**

(3)

Reference:

V. DETAILED SPECIFICATIONS

Clarification concerning chain link type:

- **Mesh to be double barbed / twisted (top and bottom)**
- **See 2017-007 Landfill & Transfer Station Fencing Invitation to Bid, Page 9 of 10 Attachment A – Existing Landfill Perimeter Fence (Reference Image)**

(4)

Reference:

V. DETAILED SPECIFICATIONS

Clarification concerning post foundations:

- **Post foundation locations to be excavated to +/-2.5 feet below finished grade.**
- **Posts to be set in concrete.**

(5)

Reference:

V. DETAILED SPECIFICATIONS

Clarification concerning post length:

- **Posts to be 8 feet long
(Set 2 feet below finished grade and extending 6 feet above finished grade)**

(6)

Reference:

X. SUBMITTAL REQUIREMENTS

Bid Date Extension:

- Sealed Bid Proposals will be received until
3:00 PM EST on Tuesday - May 16, 2017
At the Town Manager’s Office, 100 Winnacunnet Road, Hampton, NH 03842.
Sealed bid proposal envelopes must be clearly marked
“2017-007 Landfill & Transfer Station Fencing”